

Site Establishment

- The Contractor is responsible for site fencing, and signage as per Obstruction Permit and Traffic Management Plan
- Tree Protection Zone fencing to be established where necessary and approved by the City's arborist prior to work commencing.

Excavation

- In softscape, the existing surface treatment (garden or turf) shall be cut and/or removed neatly.
- In paved areas, the contractor shall remove and store paving safely, securely and neatly in a location which minimises impact to the public. Pavers should not be stacked and stored over existing tree roots or protection zones
- Mechanical excavation not to be conducted within 1m of High Pressure Gas or High Voltage power.
- All works around existing Tree Protection zones to be completed according to AS4970:2009 - Protection of Trees on Development sites. The City's Arborist to attend site under conditions dictated by the standard.
- Vacuum excavation to be utilised where appropriate around existing utilities or tree roots.
- No excavation shall be left open at the conclusion of the day's work. All works shall be left completed, made safe or alternatively filled to grade and smooth. Works areas shall be left clean and surfaces blown down. Absolutely no storage of materials within tree rootzone.
- The contractor is responsible for disposing of any excess spoil. Excess spoil or dirt is not to be stored over tree protection zones, pedestrian thoroughfares or road carriageways.